

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: The Bill Bowman Oil Company  
Address: 2640 W Road Natoma, Kansas 67651  
Phone: (785) 434-2286 M-F Operator License #: 33263  
Type of Well: ~~Oil Well~~ DH Docket #: N/A  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: December 4, 2009 (Date)  
by: KCC - District #4, Hays, Kansas Agent Pat Bedore (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
None - Plugged Well Depth to Top: N/A Bottom: N/A T.D. 3860'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 065-23581-0000  
Lease Name: Keiswetter  
Well Number: #1  
Spot Location (QQQQ): \_\_\_\_\_ - SE - NW - NE  
4069 Feet from  North /  South Section Line  
1969 Feet from  East /  West Section Line  
Sec. 35 Twp. 6 S. R. 22  East  West  
County: Graham County, Kansas  
Date Well Completed: December 5, 2009  
Plugging Commenced: December 4, 2009  
Plugging Completed: December 4, 2009

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
None - Plugged Well	N/A	0	248'	8 5/8"	248'	0
				No Production Casing		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well According to KCC - District #4's, Hays, Kansas, Instructions

1st plug @ 1950' with 25 sacks, 2nd plug @ 1190' with 100 sacks, 3rd plug @ 300' with 40 sacks, 4th plug @ 40' with 10 sacks, 30 sacks in Rathole, and 15 sacks in Mouse. Used 220 sacks total, 132 sacks Common, 88 sacks 60/40 Poz Mix, 4% Gel and 1/4# Flo Seal. Copy of Cementing Ticket attached.

Name of Plugging Contractor: Allied Cementing Company, LLC License #: 99996  
Address: P.O. Box 31 Russell, Kansas 67665  
Name of Party Responsible for Plugging Fees: The Bill Bowman Oil Company  
State of Kansas County, Osborne, ss. **KCC WICHITA**  
Owner - William "Bill" Bowman (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) William H. Bowman  
(Address) 2640 W Road Natoma, Kansas 67651

SUBSCRIBED and SWORN TO before me this 14<sup>th</sup> day of January, 2010  
Jackie J. Langholz My Commission Expires: 2-24-2013  
Notary Public

# ALLIED CEMENTING CO., LLC. 044270

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
OAKLEY

DATE <u>12-4-09</u>	SEC <u>35</u>	TWP <u>6S</u>	RANGE <u>22W</u>	CALLED OUT	ON LOCATION <u>10:45 PM</u>	JOB START <u>8:45 AM</u>	JOB FINISH <u>9:15 AM</u>
LEASE <u>KEISWETTER</u>		WELL # <u>1</u>	LOCATION <u>Hell City 7N-6E-1N-3/4W-S 2W</u>		COUNTY <u>GRAHAM</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR ROYAL DRUG  
 TYPE OF JOB PTA  
 HOLE SIZE 7 7/8" T.D. 3860'  
 CASING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE 4 1/2" DEPTH 1950'  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER SAME  
 CEMENT AMOUNT ORDERED:  
270 SKS 60/40 402 4% gel 1/2" P/L SEAL

COMMON	<u>132 SKS</u>	@	<u>13.50</u>	<u>1782.00</u>
POZMIX	<u>88 SKS</u>	@	<u>7.55</u>	<u>664.40</u>
GEL	<u>8 SKS</u>	@	<u>20.25</u>	<u>162.00</u>
CHLORIDE	_____	@	_____	_____
ASC	_____	@	_____	_____
	_____	@	_____	_____
	_____	@	_____	_____
	_____	@	_____	_____
	_____	@	_____	_____
	_____	@	_____	_____
	_____	@	_____	_____
	_____	@	_____	_____
HANDLING	<u>228 SKS</u>	@	<u>2.35</u>	<u>513.80</u>
MILEAGE	<u>10¢ PER SK/MILE</u>			<u>1710.00</u>
TOTAL				<u>4966.15</u>

**EQUIPMENT**

PUMP TRUCK CEMENTER FERRY  
 # 323-281 HELPER ANDREW  
 BULK TRUCK  
 # 396 DRIVER LARENZ  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

**RECEIVED**  
**JAN 19 2010**

REMARKS:  
25% AT 1950  
100% AT 1190  
HOLES AT 300'  
10% AT 40  
30% AT HOLE  
15% MOUSE HOLE

**KCC WICHITA**

*THANK YOU*

CHARGE TO: BILL BOWMAN OF, CO  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**SERVICE**

DEPTH OF JOB	<u>1950'</u>			
PUMP TRUCK CHARGE			<u>991.00</u>	
EXTRA FOOTAGE	_____	@	_____	
MILEAGE	<u>75 MF</u>	@	<u>7.00</u>	
MANIFOLD	_____	@	_____	
	_____	@	_____	
	_____	@	_____	
TOTAL				<u>1516.00</u>

**PLUG & FLOAT EQUIPMENT**

<u>8 7/8 old HOLE plugs</u>			<u>39.00</u>
_____	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment