

KANSAS CORPORATION COMMISSION FEB 01 2010  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD CONSERVATION DIVISION  
K.A.R. 82-3-117 WICHITA, KS

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

OPERATOR: License #: 5135  
Name: John O. Farmer, Inc.  
Address 1: P.O. Box 352  
Address 2: \_\_\_\_\_  
City: Russell State: KS Zip: 67665 + \_\_\_\_\_  
Contact Person: Marge Schulte  
Phone: ( 785 ) 483-3145, Ext. 214  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All. (If needed attach another sheet).  
Mississippi Depth to Top: 4497' Bottom: 4590' T.D. 4590' RTD  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 4561' PBDT  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 135-24,696-00-00  
Spot Description: 50' South & 130' East of NW NE NW  
SE NW NE NW Sec. 35 Twp. 16 S. R. 25  East  West  
380 Feet from  North /  South Line of Section  
1,780 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ness  
Lease Name: Horacek Well #: 1  
Date Well Completed: (drilling completed 9-19-07)  
The plugging proposal was approved on: 11-30-09 (Date)  
-by: District #1 - Jerry Stapleton (KCC District Agent's Name)  
Plugging Commenced: 12-2-09  
Plugging Completed: 12-2-09, 11:15 A.M.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surface	8-5/8"	223'	-0-
Mississippi	oil & water	production	5-1/2"	4589'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

4505' - mix 35 sks. cement, 18 gel, 150# hulls  
1800' - 160 sks. cement - circulated cement  
Top off 5-1/2" casing - 15 sks. cement  
Top off 8-5/8" casing - 5 sks. cement  
Held 500#

(Total used - 129 sks. Common cement, 86 sks. Pozmix, 18 gel, 150# hulls)

Plugging Contractor License #: 99977 Name: Quality Oilwell Cementing, Inc.  
Address 1: P.O. Box 32 Address 2: \_\_\_\_\_  
City: Russell State: Kansas Zip: 67665 + \_\_\_\_\_  
Phone: ( 785 ) 483-2025  
Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.  
State of Kansas County, Russell, ss.  
John O. Farmer III, President of John O. Farmer, Inc.  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: John O. Farmer III 1-28-10

# QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025  
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

**COPY** No. 3586

Date	12/2/09	Sec.	35	Twp.	16	Range	25 W	County	Ness	State	KS	On Location		Finish	11:15 AM	
Lease	Horacek			Well No.	1			Location	Arnold, 1 S, 1/2 W, S10							
Contractor	J+M Well Service							Owner	To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.							
Type Job	Plug							Charge To	J.O. Farmer							
Hole Size	T.D.							Street								
Csg. Size	5 1/2"							Depth								
Tbg. Size	2 7/8"							Depth								
Tool	Depth							City	State							
Cement Left in Csg.	Shoe Joint							The above was done to satisfaction and supervision of owner agent or contractor.								
Meas Line	Displace							18 gel on side CEMENT								
<b>EQUIPMENT</b>								Amount Ordered	270sx60/40 4% gel							
Pumptrk	9	No.	Cement	Helper				Paul	Common							
Bulktrk	11	No.	Driver	Driver				Doug	Poz. Mix							
Bulktrk	PV	No.	Driver	Driver				Darin	Gel.							
<b>JOB SERVICES &amp; REMARKS</b>								Calcium								
Remarks:	4505' - mix 18 gel							Hulls	200 #							
	35sx - 150# Hulls							Salt	RECEIVED KANSAS CORPORATION COMMISSION							
	1800' - 160sx Circ. Cement							Flowseal	FEB 01 2010							
	Top off 5 1/2" - 15sx							Handling								
	Top off 8 5/8" - 5sx Held 500#							Mileage								
<b>FLOAT EQUIPMENT</b>								Guide Shoe								
								Centralizer								
								Baskets								
								AFU Inserts								
								Pumptrk Charge								
								Mileage								
								Tax								
								Discount								
								Total Charge								
X Signature	Val De...															

Thank You!!

Quality Oilwell Cementing