

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9067
Name: DaMar Resources, Inc.
Address 1: 234 W. 11th St.
Address 2: P. O. Box 70
City: Hays State: KS Zip: 67601 + _____
Contact Person: Curtis R. Longpine
Phone: (785) 625-0020
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 065-21155-0000
Spot Description: _____
C NW NW NE Sec. 10 Twp. 8 S. R. 23 East West
330 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Graham
Lease Name: Jones Well #: 2
Date Well Completed: 9/29/79
The plugging proposal was approved on: _____ (Date)
by: Pat Staab (KCC District Agent's Name)
Plugging Commenced: 12/31/09
Plugging Completed: 12/31/09

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	225 276'	none
		Production	5 1/2"	3782'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method and methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

See enclosed plugging report

Plugging Contractor License #: 3152 Name: Poe Well Service
Address 1: P. O. Box 115 Address 2: _____
City: Oberlin State: KS Zip: 67749 + 0115
Phone: (785) 475-3422
Name of Party Responsible for Plugging Fees: DaMar Resources, Inc.
State of Kansas County, Ellis, ss.
Curtis R. Longpine Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____


Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 25 2010
3-25-10
CONSERVATION DIVISION
WICHITA, KS

DaMar Resources Inc

Jones #2

Graham Co Ks

KLM 3152

12-31-09

Moved in work string. Rigged up Poe Well Service. Ran 104 jts of 2 3/8 to 3414. Dug catch hole. Rigged up Quality Cementing and pumped 13 sxs gel and 50 sxs cement and 250# hulls. Pulled tubing to 2000' pumped 100 sxs and 150# hulls. Pulled to 1000' and pumped 80 sxs w/ 100# hulls.

Cement cir.

Pulled tubing. Pumped 5 sxs into 8 5/8 Pressured to 200 and shut in at 200#

Toped off 5 1/2 w 15 sxs. Rigged down and moved off.

State Man Pat Staab

Will check cement and cut off well head and clean up location next week.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 25 2010