

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34318
Name: Berexco, L.L.C.
Address 1: P. O. Box 723
Address 2: P.O. Box 20380, Wichita, KS 67206
City: Hays State: KS Zip: 67601 +
Contact Person: Robert Grant
Phone: (785) 628-6101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #:
 ENHR Permit #: _____ Gas Storage Permit #:
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2912' Bottom: 2916' T.D.: _____
Toronto Depth to Top: 2972' Bottom: 2976' T.D.: _____
L-KC Depth to Top: 3191' Bottom: 3224' T.D.: _____
ARB 3324' 3341'

API No. 15 - 167-06144-0001
Spot Description: _____
S/2 NW SW Sec. 16 Twp. 11 S. R. 15 East West
2630/650 Feet from North South Line of Section
860 4620 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Russell
Lease Name: Whitson Well #: 2
Date Well Completed: 10-13-47
The plugging proposal was approved on: 4-27-10 (Date)
by: Pat Bedore (KCC District Agent's Name)
Plugging Commenced: 4-28-10
Plugging Completed: 4-24-10
28

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surf	10 3/4	526	0
		prod	7" 24#	3221	0
		L1	5 1/2	3329'	0
		L2	4 1/2	3341'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg to 3175', pump 75 bbl rotary mud, 75 sx 60/40 pos 4% gel, 1/4# flowseal per sx w/300# hulls. Pull tbg to 1717', pump 50 sx cement w/ 200# hulls. Pull tbg to 972', pump 75 sx cement. Pull tbg to 500', pump 150 sx cement, circ to surface on 7". Pull out of hole, hook to surface casing, pressure to 200#, held. Top off 7" w/10 sx cement, hole stayed full.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.
Address 1: P. O. Box 723 Address 2: P.O. Box 20380, Wichita, KS 67206
City: Hays State: KS Zip: 67601 +
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.
State of Kansas County, Sedgwick, ss.
Robert Grant Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Robert Grant

REC
KANSAS CORP

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MAY 11
5-11-10
CONSERV.
WIC