


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Ellis County. Sec. ^{AUG 3} 13 Twp. 14S Rge. 16W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SE
Lease Owner John Lindas Oil Inc.
Lease Name Drilling A Well No. 1
Office Address 1316 Union National Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-21- 19 52
Application for plugging filed March 8-24- 19 52
Application for plugging approved March 24 19 52
Plugging commenced March 24 ~~APRIL 5~~ 19 52
Plugging completed April 5 19 52
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty
Producing formation Depth to top Bottom Total Depth of Well 3440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	208'	Cemented
				5 1/2"	3439'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filed hole to 3440' with sand
Dumped 4 sacks cement at 3430' with dump bailor
Shot off and pulled 2003' of 5 1/2" pipe
Mudded hole to 208'
Set 15' rock bridge at 208'
Dumped 15 sacks of cement at 197'
Mudded hole to 30'
Set 10' rock bridge at 30'
Dumped 10 sacks of cement at 20' to fill and cap top of surface pipe.

04-09-52

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duncan-Miller pipe pulling company
Address Hoisington, Kansas



STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, B. L. Gilmer (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) *B. L. Gilmer* Superintendent

1316 Union National Bank Bldg. Wichita, Kansas
(Address)
SUBSCRIBED AND SWORN to before me this 8th day of April, 19 52.
Edward W. Wiers
Notary Public.

My commission expires October 8, 1955

23-8390-s 8-51-20M
PLUGGING
FILE SEC 13 T 14 R 16 W
BOOK PAGE 7 LINE 31

DRILLING LOG

To: Lion Oil Company
 The Polcyn Company
 W. R. Yeager
 Garshaw Oil Company
 Feingold Oil Company
 Dr. Hugh Hamilton
 Mr. Daniel L. Brenner
 Mr. Edward G. Siebert

Lease: #1 Dreiling A

County: Ellis
 Location: SW $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$
 Section: 3-14S-16W
 Elevation: 1942 KB 1937GL

Rotary Total Depth: 3444'

Commenced: 1-29-52 Completed: 2-12-52

Casing: 8 5/8" @ 208 with 100 sacks of cement and 2 sacks of Calcium Chloride; 5 1/2" @ 3439' with 100 sacks of cement.

Contractor: John Lindas Oil, Inc. Rig. #2
 1316 Union National Bank Building
 Wichita 2, Kansas

FIGURES INDICATE BOTTOM HOLE FORMATION

0	to	60	Soil Shale & Shells
60		118	Sand & Shale
118		150	Shale & Shells
150		415	Shale
415		425	Iron
425		525	Shale & Sand
525		670	Sand
670		700	Shale Red
700		745	Sand & Shale
745		1033	Shale & Shells
1033		1078	Anhydrite
1078		1375	Shale
1375		1500	Broken Lime & Shale
1500		1815	Shale & Shells
1815		1910	Lime
1910		1985	Lime & Shale
1985		2120	Lime
2120		2140	Shale & Lime
2140		2430	Lime
2430		2512	Lime & Shale
2512		2680	Shale & Shells
2680		2865	Shale & Lime
2865		3444	Lime T.D.

State of Kansas)
)SS
 County of Sedgwick)

I, the undersigned, being duly sworn on oath, state that the above statement and log is a true and correct record of the well drilled by John Lindas Oil, Inc. at the location above described.

Edward W. Wiers

Subscribed and sworn to before me, this 12th day of February, 1952.

PLUGGING
 FILE SEC 13 T 14 R 16W
 BOOK PAGE 7 LINE 31

Catherine Rancy
 Notary Public

My Commission expires March 25, 1952.