


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-051-01228-00-00

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 3 Twp. 14 Rge. (E) 16 (W)  
Location as "NE/CNW%SW%" or footage from lines SE SE SW  
Lease Owner Strata Drilling, Inc., Leo J. Dreiling Oil Co.  
Lease Name Griese Well No. 1  
Office Address Box 355, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 24 1958  
Application for plugging filed May 24 1958  
Application for plugging approved May 24 1958  
Plugging commenced May 24 1958  
Plugging completed May 24 1958  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eidon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3480' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole as follows: Plugged at 450' with 20 sacks of cement through drill pipe, plug at 180' with 15 sacks of cement, plug at 40' with 10 sacks of cement. Job completed at 10:00 A. M. on May 24, 1958.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 2 1958  
06-02-58  
T.C.N. DIVISION


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling, Inc.  
Address Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Charles W. Steincamp (employee of owner) or (owner ~~or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp  
Box 355, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 19 58

My commission expires December 14, 1961  
Elaine H. Taylor  
Elaine H. Taylor Notary Public.



PLUGGING  
FILE SEC. 3 T. 14 R. 16w  
BOOK PAGE 105 LINE 22

DRILLERS LOG

#1 Griese

CASING RECORD: 206' of used 8-5/8" surface casing. COMPANY: Strata Drilling, Inc. DESCRIPTION: SE SE SW Section 3-14-16W  
 CONTRACTOR: Strata Drilling, Inc. Ellis County, Kansas

TOTAL DEPTH: 3480' COMMENCED: May 14, 1958 ELEVATION: 1944' KB  
 COMPLETED: May 24, 1958

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	560	Ran 206' (10 joints) of used 8-5/8" surface casing; cemented with 150 sacks of cement, 2% C. C. <u>DST #1</u> Packer set at 3188'. Total Depth 3240'; misrun packer failure. <u>DST #2</u> Packer set at 3172'. Total Depth 3240'; tool open 20 minutes, mud leaking by packer. Reset packer weak blow 5 minutes. Recovered 95' mud. BHP 725 lbs. in 15 minutes. <u>DST #3</u> Packer set at 3246'. Total Depth 3279'; tool open 1 hour, fair to weak blow throughout. Recovered 140' muddy water. IFP 0 lbs. FFP 75 lbs. BHP 675 lbs. in 20 minutes. <u>DST #4</u> Packer set at 3438'. Total Depth 3450'; tool open 25 minutes, weak blow 4 minutes. Recovered 12' mud, slightly oil specked. BHP 810 lbs. in 15 minutes. <u>DST #5</u> Packer set at 3449'. Total Depth 3459'; tool open 30 minutes, weak blow 10 minutes, by-passed tool weak blow 6 minutes. Recovered 25' mud, no show of oil. BHP 625 lbs. in 20 minutes.
Sand	560	690	
Red Bed	690	810	
Shale & Shells	810	1040	
Anhydrite	1040	1070	
Shale & Shells	1070	1750	
Shale & Lime	1750	2100	
Shale	2100	2180	
Lime & Shale	2180	3020	
Lime	3020	3140	
Lime & Shale Breaks	3140	3215	
Lime	3215	3480	
TOTAL DEPTH 3480'			
Top Anhydrite	1040'	( 904)	
Top Topeka	2879'	(- 935)	
Top Heebner	3136'	(-1192)	
Top Toronto	3160'	(-1216)	
Top Lansing	3184'	(-1240)	
Base of Kansas City	3419'	(-1475)	
Top Chert Conglomerate	3431'	(-1487)	
Top Arbuckle	3435'	(-1491)	

STATE OF KANSAS )  
 ) ss:  
 COUNTY OF BARTON )

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
 Charles W. Steincamp, Pres.

Subscribed and sworn to before me this 26th day of May, 1958.

*Elaine H. Taylor*  
 Elaine H. Taylor, Notary Public

