

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051-22,455-00-00

LEASE NAME Lang

WELL NUMBER 2-C

3630 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 6 TWP. 14S RGE. 17W (E) or (W)

COUNTY Ellis

Date Well Completed 6-24-81

Plugging Commenced 3-4-88

Plugging Completed 3-10-88

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Dreiling LTD

ADDRESS 410 17th St. Suite 1140 Denver, CO 80202

PHONE# (303) 623-6144 OPERATORS LICENSE NO. 5804

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-10-88 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? yes-by operator not, is well log attached? _____

Producing Formation Kansas City Depth to Top 3346 Bottom 3404 T.D. 3650

Plugged back to 3618

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|--------------|------|--------|---------|-------------------------|
| | | 0 | 285 | 8 5/8 | 6/1981 | |
| | | 0 | 3615 | 4 1/2 | 6-24-81 | 3-7-88 600 ft recovered |
| | | Perforations | | 3400 - | 3404 | |
| | | | | 3346 - | 3350 | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

(Over)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bill's Well Service License No. 6997

Address Box 37 Codell, KS 67630

STATE OF Kansas COUNTY OF Ellis, ss.

Gary E Geist (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary E Geist

(Address) _____

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 88

Donald J. Simons
 Notary Public

My Commission Expires:  7-11-91

RECEIVED
 STATE CORPORATION COMMISSION
 APR 21 1988
 01-21-88
 CONSERVATION DIVISION
 Wichita, Kansas

Method of Plugging-

Dumped in sand with a dump baler to 3300 feet to cover perforations. Plugged with 5 sacks cement. Pulled on $4\frac{1}{2}$ " casing, parted at 80,000#. Recovered 16 joints or 640 feet. Moved in double drum. Set tubing at 1137 feet. Shot 3 perforations at 80 degrees each at 1155 feet. Mixed 50 sacks common cement. Pulled tubing to 450 feet. Mixed 75 sacks ATL with 4 sacks hulls. Cement circulated. Came out with tubing. Went down $8\frac{5}{8}$ " casing. Mixed 75 sacks ATL cement with 1 sack hulls. Maximum pressure 900#. Shut in 700#.