

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-23804-0000

LEASE NAME Prewo

WELL NUMBER 1

SPOT LOCATION SE SE SE

SEC. 6 TWP. 14 RGE. 17 ~~XXX~~ (W)

COUNTY Ellis

Date Well Completed 2-25 -84

Plugging Commenced 2-25-84

Plugging Completed 2-25-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Weilert Oil Company, Inc.

ADDRESS 2604 E. General Hays Rd., Hays, Ks. 67601

PHONE # (913)-625-2888 OPERATORS LICENSE NO. 8640

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks. 67601

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	261	8 5/8"	261	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. total 180 sacks with 2 sacks flow seal.

1st. Plug set at 1270' with 20 sacks common cement 50-50 Poz 6%Gel 3%Calcl.

2nd. Plug set at 700' with 100 sacks common cement 50-50 Poz 6%Gel 3% Cal cl.

3rd. Plug set at 270' with 40 sacks common cement 50-50 Poz 6%Gel 3%Cal cl.

4th. Plug set at 40' with 10 sacks common cement 50-50 Poz 6%Gel 3%Cal cl.

(If additional description is necessary, use BACK of this form.)

10 sacks in rathole.

Name of Plugging Contractor Allied Cementing, Inc. License No. \_\_\_\_\_

Address Russell, Ks.

STATE OF Kansas COUNTY OF Graham, ss.

Jerry M. Helberg

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. Wahpeme God.

RECEIVED

STATE CORPORATION COMMISSION

(Signature) Jerry M. Helberg

(Address) Box 32, Morland, Ks. 67650

MAR 23 1984

SUBSCRIBED AND SWORN TO before me this 9th day of March, 1984

CONSERVATION DIVISION  
Wichita, Kansas

Coleen A. Waggoner  
Coleen A. Waggoner, Notary Public

My Commission expires: March 11, 1986