

15-051-30259-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ellis County, Sec. 6 Twp. 14S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines SE SW NE

Lease Owner Rains & Williamson Oil Company

Lease Name Younger Well No. 1

Office Address 1425 Wichita Plaza Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-9- 19 66

Application for plugging filed 4-9- 19 66

Application for plugging approved 4-9- 19 66


Plugging commenced 4-9- 19 66

Plugging completed 4-9- 19 66

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3619 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	218.47'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 540'. Cement through drill pipe with 20 sx. and mud back.
Pushed plug to 200' and cement with 20 sx., mud back to 40', capped with
10 sx.

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.


Wilson Rains, Partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
1425 Wichita Plaza Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 15th day of April, 19 66

Mary J. Brown
Mary J. Brown Notary Public.

My commission expires March 3, 1970



ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co.
#1 Younger
SE SW NE Sec. 6-14S-17W
Ellis County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
COMMENCED: 3-30-66
COMPLETED: 4-9-66
REMARKS: Set 218.47' of 8-5/8"
surface pipe with
165 sacks of GL 3.

FORMATIONS:

Surface Soil	20'
Sand & Shale	219'
Shale & Shells	675'
Sand	880'
Red Bed	1065'
Red Bed & Shale	1223'
Anhydrite	1263'
Shale	1889'
Lime	1939'
Lime & Shale	2140'
Lime W/Shale	2305'
Lime	2455'
Lime & Shale	2810'
Lime W/Shale	2980'
Lime & Shale	3165'
Lime W/Shale	3209'
Lime	3260'
Lime W/Shale	3378'
Lime	3557'
Arbuckle Lime	3619'
Total Depth (D & A)	3619'

RECEIVED
STATE CORPORATION COMMISSION
APR 18 1966
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 15th day of April, 1966.

My Commission Expires:
March 3, 1970

Mary J. Brown
Mary J. Brown Notary Public

