


15-051-21864-05-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County. Sec. 6 Twp. 14S Rge. 17 XX
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SE NE
Lease Owner Three G Royalty
Lease Name Younger Well No. 1
Office Address P. O. Box 1214 Great Bend, Kans.
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole



Locate well correctly on above
Section Plat

Date Well completed March 20 19 80
Application for plugging filed March 20 19 80
Application for plugging approved March 20 19 80
Plugging commenced 9:00 P. M. March 20 19 80
Plugging completed 10:00 P. M. March 20 19 80
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation Depth to top Bottom Total Depth of Well 3555
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

600' W/70 sx. 50/50 Poxmix 6% Gel
200' W/20 sx. " " "
10' W/40 sx. " " "
5 sx. in rat hole " "

RECEIVED
STATE CORPORATION COMMISSION

APR - 3 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
L. D. Davis (employee or owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) L. D. Davis Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 80

Bessie M. Dewerff
Bessie M. Dewerff Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

THREE G ROYALTY - OPERATOR

YOUNGER # 1
SE SE NE
Sec. 6-14S-17W
ELLIS COUNTY, KANSAS

T. D. 3555
ELEV. 2006 K.B.

COMMENCED: 3-15-80
COMPLETED: 3-20-80

CASING

8-5/8" set at 212'

CEMENT

W/140 sx. 60/40 Pozmix, 2% Gel, 3% CC

FORMATION

DEPTH

Surface Shale	0 - 212
Shale	212 - 666
Sand	666 - 851
Shale & red bed	851 - 1207
Anhy.	1207 - 1245
Shale & Shells	1245 - 2020
Shale W/Lime	2020 - 2245
Shale & Lime	2245 - 3021
Lime W/shale	3021 - 3310
Lime & Shale	3310 - 3420
Lime	3420 - 3555
R.T.D.	3555

TOPS

Heebner	3260	(-1255)
Toronto	3282	(-1276)
Lansing	3306	(-1301)

AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON)_{ss}

I Certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.

Don Popp
Don Popp

RECEIVED
STATE CORPORATION COMMISSION
APR - 3 1980
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn before me on this 28th day of March, 1980.

My appointment expires: 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff