



15-167-20463-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of L. J. Dreiling & Sons has this  
date requested permission to plug the following described well:

Mr. Leo J. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil Inc. & Borrell

Complete Address: R. R. # 2, Victoria, Kansas

Lease Name: Kaufman Well No. # 1

Location: NW SW SW Sec. 11 Twp. 14 Rge. 11 (E)(W) W

County: Russell Total Depth 2925 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bill Draper was instructed to plug the well as follows:

8 5/8" 267' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 260' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & 10 sax cement with

Allied Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don Truman  
Conservation Division Agent