



15-167-20456-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1971
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bill Draper of L. J. Dreiling & Sons has this date requested permission to plug the following described well:

Mr. L. J. Dreiling guarantees payment of the plugging fee.

Operator's full Name: ^{BORELL}
~~Borell~~ & Dreiling Oil, Inc.

Complete Address: R. R. # 2, Victoria, Kansas

Lease Name: Charvat "C" Well No. # 1

Location: SE SE SE Sec. 3 Twp. 14 Rge. 11 (E)(W) W

County: Russell Total Depth 3450 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bill Draper was instructed to plug the well as follows:

8 5/8" 308' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 300' & displaced 20 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to

base of cellar.

Very truly yours,

Don L. Brown
Conservation Division Agent