



15-167-20566-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1972

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Company has this
date requested permission to plug the following described well:Mr. Albert W. Borell guarantees payment of the plugging fee.Operator's full Name: Albert W. BorellComplete Address: Box 391, Wilson, KansasLease Name: Gable-Binger Well No. # 1Location: SW SE SE Sec. 2 Twp. 14 Rge. 11 (E)(W) WCounty: Russell Total Depth 3460 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Jerb Ogle was instructed to plug the well as follows:8 5/8" csg. 347' Cwc.Circulated hole with heavy mud to 480', set plug, & displaced40 sax cement thru drill pipe. Mud to 320' & displaced 25 sax cementthru drill pipe. Mud to 40', 1/2 sax hulls, plug, & 10 sax cement~~thru drill pipe~~ with Allied Cementing Company's pump truck, cementing

to base of cellar.

Very truly yours,

Conservation Division Agent