

State of Kansas



FORM CP-2

15-167-21850-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Leonard Williamson of Duke Drilling Co. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Roy Vonfeldt

Complete Address: 524 St. John, Russell, Ks. 67665

Lease Name: Schmidt Well No. #1

Location: NE NW NE Sec. 32 Twp. 14 Rge. 15 (E)

County: Russell Total Depth: 3410'

Abandoned Oil Well Gas Well Input Well SWD Well D&A xxx

Other well as hereafter indicated: _____

Mr. Williamson was instructed to plug the well as follows:

8 5/8" 248' S.P. cue. w/150 sacks common-2%Gel-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @720' w/70 sacks cement

2nd plug @240' w/40 sacks cement

3rd plug-Solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

Very truly yours,


Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1981

12-2881
CONSERVATION DIVISION
Wichita, Kansas