

State of Kansas



FORM CP-2

15-167-21919-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Stanley Lingreen of Revlin Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Crude Producers, Inc.

Complete Address: Box 55, Russell, Kansas 67665

Lease Name: Zedja Well No. #1

Location: 990' FEL 990' FSL- SW Sec. 7- Twp. 14 Rge. 15 (E) (W)

County: Russell Total Depth: 3420'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A^X ☐

Other well as hereafter indicated:

Mr. Lingreen was instructed to plug the well as follows:

8 5/8"-215' s.p. cuc. w/160 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement

Circulate 10 sacks of cement in rat hole.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

JUN -2 1982

CONSERVATION DIVISION
Wichita, Kansas

Conservation Division Agent