

15-167-05678-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 64-24
LOCATION SE-~~SE~~^{SW}W/2-SE
SEC. 7 TWP14 RGE. 13W

Dry Hole _____ Abandoned Oil Well ~~***~~ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Ehrlich "B"
Operator Chester Loving Address 907 East Second St. Russell, Kansas.
Field _____ County Russell

Total Depth 2396' Feet.

Plugging Contractor Arnett Casing Pulling Company

Plugging Contractor's License No. 265

Address Hoisington, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe - None. 7" set @ 2396' cem. 75 sx. perforated @ 2358'
Sand back to 2348' and 5 sx. cem. with dump bailer. Shot 7' off @ 1600'
and pulled same. Pulled 7" pipe up to 640' from top, pumped 10 sx. jell
mud into the hole, then pulled pipe up to 286' from top, 67" pipe was
full of jell mud so we pumped in 42 sx. cem. , pressure built up to
500# , so we pulled out 2 more joints of 7" pipe and pumped in 18 sx. cem.
Then next day we bailed out fluid to 25' from top, set rock bridge and
10 sx. cem. to base of cellar.

(Halliburton pump truck was used)

Milton Galyard
District Conservation Agent

RECEIVED Date 6-26-56
STATE CORPORATION COMMISSION

JUN 29 1956
06-29-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 7 T. 14 R. 13W
BOOK PAGE 64 LINE 24