

15-167-05680-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 64-25

LOCATION SW-SE-SE

SEC. 7 TWP 14 RGE 13W

Dry Hole _____ Abandoned Oil Well *** Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Ehrlich "C"

Operator Chester Loving Address 907 East Second St.
Russell, Kansas.

Field _____ County Russell

Total Depth 2406' Feet.

Plugging Contractor Arnett Casing Pulling Company.

Plugging Contractor's License No. 265

Address Hoisington, Kansas.
(Describe briefly the manner in which the well was plugged)

Surface pipe - None. 7" set @ 2397' cem. 75 sx.. Plug pumped to 2380'
and perforated @ 2365'. Sand back to 2355' and 5 sx. cem. with dump
bailer. Shot 7" off @ 1425' and pulled same. Pulled 7" pipe up to 600'
from top, pumped 10 sx. jell mud into pipe at that depth. Then pulled
pipe up to 285' from top, pumped in 5 more sx. jell mud and followed
up with 60 sx. cem.. Then next day bailed out water and mud to 25' from
top, and filled hole with 21 sx. cem. to base of cellar.

Halliburton pump truck was used.

Milton Anderson
District Conservation Agent

Date 6-23-56

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1956

06-26-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 7 T 14 R 13W
BOOK PAGE 64 LINE 25