

15-167-05679-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 64-23

LOCATION SE-SE-SE

SEC. 7 TWP. 1 RGE. 13W

Dry Hole _____ Abandoned Oil Well *** Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Ehrlich "C"

Operator Chester Loving Address 907 East Second St. Russell, Kansas.

Field _____ County Russell

Total Depth 2411' Feet.

Plugging Contractor Arnett Casing Pulling Co.

Plugging Contractor's License No. 265

Address Holsington, Kansas, Russell, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe - None. 7" set @ 2411' cem. 75 sx. Perforated @ 2376'.
Sand back to 2366' & 6 sx. cem. with dump bailer. Shot 7" off @ 1408'
and pulled all of pipe but 300'. Took Mr. Arnett's, Gardner & Denver
pump, and pumped in 15 sx. jell mud and followed with 60 sx. cem. .
Then pulled rest of 7" pipe out. Next day bailed out water and heavy
mud to 35' from top, set rock bridge and 28 sx. cem. to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1956
CONSERVATION DIVISION
Wichita, Kansas

Milton G. Schardt
District Conservation Agent

Date 6-20-56

06-22-56

PLUGGING
FILE SEC. 7 T. 14 R. 13W
BOOK PAGE 64 LINE 23