

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
Rev. 5-5-81

OCT - 1 1981

CONSERVATION DIVISION
Wichita, Kansas

API Number 15-167-21780 ✓ 00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Orville Kaufman

Complete Address RFD #1, Great Bend, Kansas 67530

Lease Name Lester Well No. #1

Location SE/NE/NE-SE/NE/NE Aug Sec. 30 Twp. 14 Rge. 11 (East) (West)

County Russell Total Depth 3207'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Duke Drilling Company, Inc.

Address Box 823, Great Bend, Kansas 67530 License No.

Operation Completed: Hour: 8:00AM Day: 27th Month: Sept. Year: 19 81

Plugging Operations attended by Agent? All Part None X

The above well was plugged as follows:

8 5/8"-250' sp. cuc. w/165 sacks common 50/50 posmix-2% Gel.-3% Cal. Cl.
Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug. Spotted
with drill stem with heavy mud between all plugs.

1st plug @ 720' w/ 70 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/ 10 sacks cement

5 sacks of cement in rat hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-28-81

INV. NO. 8151-W

Signed: Gilbert R. Lohr

Conservation Division Agent