

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 167-21,272-00-00

12-26-78

Operator's Full Name Saline Basin Petr. Co.

Complete Address 119 S. Santa Fe Salina, Kansas 67401

Lease Name Ethel Herber Well No. 2

Location SW NW NW Sec. 29 Twp. 14 Rge. 11 (EX) (W) X

County Russell Total Depth 2855'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated _____

Plugging Contractor Shields Drlg. Co., Inc. & Allied Cementing Co.

Address Shields Bldg. Russell, Kansas 67665 License No. _____

Operation Completed: Hour 1:30 AM Day 21 Month 12 Year 1978

The above well was plugged as follows:

- Filled hole with mud and spotted 50 sx cement at 420'.
- Filled hole with mud and spotted 25 sx cement at 210'.
- Filled hole with mud to 40' and 1/2 sx hulls, plug, and
- 10 sx cement to bottom of celler.
- 2 sx cement in rat hole.
- 2 sx cement in mouse hole.
- 223' of 5 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: David Rankin
Well Plugging Supervisor

DATE 12-28-78
INV. NO. 8841-W