

15-051-20722-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

49  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Don E. Pratt  
Complete Address Box 370 Hays, Kansas 67601  
Lease Name Polcyn Well No. 1  
Location APP C SW SE NE Sec. 10 Twp. 14 Rge. (E) (W) 16  
County Ellis Total Depth 3439'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Dreiling Drlg.  
Address Victoria, Kansas License No.         
Operation Completed: Hour 1.30 P Day 9 Month 4 Year 1971

The above well was plugged as follows:

RTD 3439' 8 5/8 csg set at 164' cwc  
Gunned pits, circulated heavy mud, set cementing plug at 1000' and displaced 25 sk  
cmt thru drill pipe. Heavy mud to 500' set cementing plug and displaced 50 sk cmt  
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 25 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben Z. Muesel  
Well Plugging Supervisor

DATE 4/13/71  
INV. NO. 3552-W