

15-051-20464-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Range Oil Co.
Complete Address 402 Insurance Bldg., Wichita, Kansas 67202
Lease Name John Kipped Well No. 1
Location NE SE NE Sec. 6 Twp. 14 Rge. (E) (W) 16
County Ellis Total Depth 3505
Abandoned Oil Well Gas Well Input Well SWD Well D & A XXX
Other well as hereafter indicated
Plugging Contractor Sage drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 6:30 P Day 19 Month 7 Year 1969

The above well was plugged as follows:

RTD 3505' 8 5/8 csg set at 214' cwc 160 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plugged rat hole with 2 sk cmt.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above was plugged as herein stated.

INVOICED

CONSERVATION DIVISION
Wichita, Kansas

Signed: Leo J. Moorey
Well Plugging Supervisor

DATE

7/23/69

INV. NO.

134-W