

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22621-00-00 ✓

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Knight Oil Company

Complete Address Box 335, Victoria, Kansas 67671

Lease Name Dreiling Well No. #1

Location E/2-SE-SE Sec. 6 Twp. 14 Rge. 16 (East) (West)

County Ellis Total Depth 3500'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Helberg Oil Company

Address Box 32, Morland, Kansas 67650 License No. \_\_\_\_\_

Operation Completed: Hour: 11:30 AM Day: 26 Month: Sept. Year: 19 81

Plugging Operations attended by Agent? All xxx Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

8 5/8"-204' sp. cnc. w/125 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem-with heavy mud between all plugs.

1st plug @ 780' with 70 sacks cement

2nd plug @ 210' with 40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' with 10 sacks cement

5 sacks of cement in rat hole.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 10-29-81

Signed: [Signature]  
Conservation Division Agent

INV. NO. 8147-W