

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 33-2

LOCATION SE SE SE

SEC. 6 TWP. 14 RGE. 16

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of: 1401 East 20th

Well No. 1 Lease _____ Dreiling Great Bend, Kans

Operator Victor Drg, ~~SO~~ INC, Address 501 Koch Bldg Wichita,

Field _____ County Ellis

Total Depth 3480 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 158' circulated with cement. 5 1/2" at 3468' with
150 sax cement behind.

Sand to 3460', set 4 sax cement with dump bailer. pulled
2700' 5 1/2", pumped hole full commercial mud (55 sax). pumped
cementing plug to 185', followed by 60 sax cement. Cement
185' to 0'.

Mudding and Cementing by Halliburton Co.

Eldon J. ...
District Conservation Agent
Date 5-14-54

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1954
05-17-54
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 6 T 14 R 16W
BOOK PAGE 33 LINE 2