

15-167-00269-00-00

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION C SW/4

SEC. 13 TWP. 14 RGE. 12W

Dry Hole \*\*\*\* Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Herbel

Operator Advance Drilling Company Address Box 44. Russell, Kansas.

Field \_\_\_\_\_ County Russell

Total Depth 1593' Feet.

Plugging Contractor Advance Drilling Company.

Plugging Contractor's License No. \_\_\_\_\_

Address Box 44. Russell, Kansas.

(Describe Briefly the manner in which the well was plugged)

Surface pipe - 10" @ 53' Not Cemented. 8 5/8" @ 372' Not Cemented  
and 7" @ 646' Not Cemented. Had Halliburtan pump heavy mud falling hole  
to 646' from top, started 7" pipe, then filled hole with mud to top,  
then pulled 7" pipe out. Pulled 8 5/8" pipe up to 300' from top set plug  
rock bridge & run 2" tubing & set on bridge. Pulled 8 5/8" pipe out. Had  
Halliburtan tie into tubing and pump in 50 sx. cem. for fresh water plug.  
Pulled tubing out. Next day bailed light fluid off and pulled 10" pipe out  
& mud up to 30' from top, set plug, rock bridge and 16 sx. cem. to base of  
cellar.

Milton Schmitt  
District Conservation Agent

Date 5-6-57

RECEIVED  
STATE CORPORATION COMMISSION

MAY 9 - 1957  
05-09-1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 13 T. 14 R. 12W  
BOOK PAGE 11 LINE 41