

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SE

SEC. 3 ^{ADSKA} ~~15~~ TWP. 14 RGE. 16

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. A-1 Lease Dreiling

Operator John Lindas Oil Co. INC. Address Wichita, Kans

Field _____ County Ellis

Total Depth ~~3440~~ 3444 Feet:

(Describe briefly the manner in which the well was plugged)

8 5/8" at 208' circulated with 100 sax cement - 5 1/2" at 3440'

with 100 sax cement behind.

Filled with chat to 3430', set 4 sax cement with dump bailer.

pulled 2000' 5 1/2", mudded hole to 208', set plug, rock bridge and

15 sax cement, mud to 35', set rock and 10 sax cement to bottom

cellar.

PLUGGING
FILE SEC 13 T 14 R 16
BOOK PAGE 7 LINE 31

APR 10 1952
DIVISION
Kansas

Edmund Perry
District Conservation Agent
Date 4-5-52