

15-051-19457-00-01

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasMAR 13 1964
03-13-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Francis J. Giebler

Complete Address: 53 S Kansas Russell, Kansas

Lease Name Anna Dreiling Well No. 1

Location SE SE SE Sec. 3 Twp. 14 Rge. (E) (W) 16

County Ellis Total Depth 3210

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons & United Cementing Co

Address: Russell, Kansas License No. 9

Operation Completed: Hour 5PM Day 7 Month 3 Year 64

The Above well, was plugged as follows:

8 5/8" 205' circulated with cement - 5 1/2" 3210' with 175 sax cement perforated at 2901'.

Filled with sand to 2890', set 4 sax cement with dump bailer - pulled

2646' 5 1/2" to 560', circulated hole with heavy gel mud through 5 1/2" at 560'

(30 sax Gel) displaced 20 sax cement through 5 1/2" at 480', heavy mud to

200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set

bridge and 10 sax cement to bottom cellar.

~~Mudding and cementing by United Cementing Co pump truck.~~

I hereby certify that the above well was plugged as herein stated.

Signed: *Edmond Little*
Well Plugging Supervisor**INVOICED**DATE 3/13/64INV. NO. 8483-W