

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 10-39

LOCATION SE NW NW

SEC. 1 TWP. 14 RGE. 16

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Berens

Operator West Supply Co Address Chase, Kans

Field _____ County Ellis

Total Depth 3468 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1020' circulated with cement, 5 1/2" at 3460

cemented,

Filled with chat to 3450', run 4 sax cement with dump

bailer, pulled 2400' 5 1/2", mudded hole to 250', set

wood plug, rock and 15 sax cement, mudded hole to

35' set rock and 10 sax cement to bottom cellar,

RECEIVED
PLUGGING
Conservation Div.
FILE SEC 1 T 14 R 16
BOOK PAGE 10 LINE 3950

J. Edward Perry
District Conservation Agent
Date 6-9-50

STATE CORPORATION
COMMISSION
KANSAS

06-17-50