

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-167 -21;850 -00-00 *K*

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Roy Vonfeldt

Complete Address 524 St. John, Russell, Ks. 67665

Lease Name Schmidt Well No. #1

Location NE NW NE Sec. 32 Twp. 11 Rge. 15 (East) (West)

County Russell Total Depth 3410'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co. Inc.

Address 818 Main Box 823 Great Bend, Ks. 67530 License No.

Operation Completed: Hour: 10:00 AM. Day: 22th Month: Dec. Year: 19 81

Plugging Operations attended by Agent?: All Part None XXX

The above well was plugged as follows:

8 5/8" 248' S.P. cuc. w/150 sacks common-2% Gel-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug-Solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1981
12-28-81

I hereby certify that the above plugging instructions were given as written and stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 1-21-82

INV. NO. 9102-u