

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-2200547-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name D Oil, Inc.

Complete Address R. R. #1, Victoria, Kansas 67671

Lease Name Kuhn Well No. #1

Location NE-^{SW}SE-NW DNRCC Sec. 17 Twp. 14 Rge. 16 (East) (West)

County Ellis Total Depth 3420'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XXX

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Inc.

Address R. R. #1, Victoria, Ks. 67671 License No.

Operation Completed: Hour: 11:40AM Day: 2nd Month: Sept. Year: 1981

Plugging Operations attended by Agent? All X Part None

The above well was plugged as follows:

8 5/8"-170' sp. Cuc. w/110 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" Plug.

Spot with drill stem-with heavy mud between all plugs.

1st Plug @ 630 ft. with 70 sacks cement

2nd Plug @ 160 ft. with 40 sacks cement

3rd Plug-solid bridge of hulls and plug @ 40 ft. with 10 sacks cement.

5 sacks of cement in rat hole and 5 sacks of cement in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION

SEP - 4 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

DATE 10-28-81

Signed: [Signature]
Conservation Division Agent

INV. NO. 80870