

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 08 1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 051-21,354 - 0878 CONSERVATION DIVISION  
Wichita, Kansas  
of this well)

Operator's Full Name Ernst & Steinle Oper.

Complete Address 1025 Main, Russell, Kansas

Lease Name Rohleder Well No. 1

Location SE NW NE Sec. 17 Twp. 14 Rge. (E) (W) 16

County Ellis Total Depth 3150'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Emphasis Drlg.

Address Russell, Kansas License No.       

Operation Completed: Hour 4:15 P Day 4 Month 8 Year 1977

The above well was plugged as follows:

RTD 3150' 8 5/8 csg set 214' cwc 150 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 210' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 8-11-77

IN. NO. 5631-W

Signed: [Signature]  
Well Plugging Supervisor