

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 34-30

LOCATION SW SE NE

SECT 17 TWP. 14 RGE. 16

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of: _____

Well No. 1 Lease Rohleder

Operator Musgrove Pet Corp. Address 518 Pet Bldg Wichita,

Field _____ County Ellis

Total Depth 3435 Feet.

Plugging Contractor Jayhawk Pipe Pulling

Plugging Contractor's License No. 19

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 221' circulated with cement - 5 1/2" at 3423' with

130 sax cement behind. Baker plugs to 3265' - perforated at

3215'

Filled with sand to 3200', set 4 sax cement with dump bailer,

pulled 2550' 5 1/2" - mud to top with commercial mud (35 sax)

pumped cementing plug to 220', followed by 70 sax cement.

Cement 220' to 0'.

Mudding and cementing by Halliburton Co.

PLUGGING
FILE SEC 17 T 14 R 16W
BOOK PAGE 34 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1954
05-27-54
CONSERVATION DIVISION
Wichita, Kansas

J. Gordon
District Conservation Agent
Date 5-25-54