

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -051 -21,369 -00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1977  
for this well  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Ernst & Stehle Operations  
Complete Address 1025 Main, Russell, Kansas  
Lease Name Rohleder Well No. 2  
Location SE SW NE Sec. 17 Twp. 14 Rge. (E) (W) 16  
County Ellis Total Depth 3432'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Emphasis Drlg.  
Address Russell, Kansas License No.         
Operation Completed: Hour 8:30 A Day 17 Month 8 Year 1977

The above well was plugged as follows:

RTD 3432' 8 5/8 csg set 182' cwc 150 sk. Flg. Mat. 50-50 poz 2% total gel.  
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.  
Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leo Massey  
Well Plugging Supervisor

DATE 8-18-77  
INV. NO. 5672-W