

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 051 - 21,342 - 00 - 00 CONSERVATION DIVISION  
(Wichita, Kansas  
for this well)

Operator's Full Name Euwer Petroleum Co. & Parrish Oil Co.

Complete Address Suite 206 Litwin Bldg, 110 N. Market., Wichita, Kansas

Lease Name Werth Well No. 1

Location SW NE NW Sec. 15 Twp. 14 Rge. (E) (W) 16

County Ellis Total Depth 3466'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drlg.

Address Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 10:45 A Day 10 Month 7 Year 1977

The above well was plugged as follows:

RTD 3466' 8 5/8 csg set 257' cwc 150 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 7-13-77

INV. NO. 547040