

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-05+-22649-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Edward P. Leiker I.T.D.

Complete Address Munior Route, Box 17, Hays, Kansas 67601

Lease Name Robben Well No. #1

Location NE/SE/SE Sec. 11 Twp. 14 Rge. 16 (East) (West)

County Ellis Total Depth 3431'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Emphasis Oil Operations

Address Box 501, Russell, Ks. 67665 License No. _____

Operation Completed: Hour: 5:30PM. Day: 21st Month: Oct. Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8"-168' s.p. cuc. w/110 sacks cement-2% Gel-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 780' w/70 sacks cement

2nd plug @ 150' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1981

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 11-23-81

INV. NO. 8354-W

Signed: [Signature]
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas