

Corrected copy

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. \_\_\_\_\_

TYPE: SIDE ONE

DOCKET NO. NP \_\_\_\_\_

(Rules 82-3-130 and 82-3-107) This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F \_\_\_\_\_ Letter requesting confidentiality attached.
C \_\_\_\_\_ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)\*\*\*Check here if NO logs were run \_\_\_\_\_.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 8640 EXPIRATION DATE May 1985
OPERATOR Weilert Oil Company, Inc. API NO. 15-051-23804-00-00
ADDRESS 2604 E. General Hays Rd. COUNTY Ellis
Hays, Ks. 67601 FIELD EXT/Younger SW

\*\* CONTACT PERSON Mike Weilert PROD. FORMATION
PHONE 913-625-2888 Indicate if new pay.

PURCHASER LEASE Prewo
ADDRESS WELL NO. 1

DRILLING Helberg Oil Company WELL LOCATION SE SE SE
CONTRACTOR RECEIVED 330 Ft. from South Line and
ADDRESS Box 32 STATE CORPORATION COMMISSION 330 Ft. from East Line of (E)
Morland, Ks. 67650 the (Qtr.) SEC 6 TWP 14 RGE 17 (W).

PLUGGING Allied Cementing MAY 17 1984
CONTRACTOR CONSERVATION DIVISION
ADDRESS Russell, Ks. Wichita, Kansas

WELL PLAT table with 4x4 grid and a dot in the bottom right cell.

(Office Use Only)
KCC [checked]
KGS [checked]
SWD/REP
PLG.
NGPA

TOTAL DEPTH 3593' PBTD
SPUD DATE 2-16-84 DATE COMPLETED 2-25-1984
ELEV: GR 2027' DF KB 2032'

DRILLED WITH (CABLE) (ROTARY) (OTHER) TOOLS.
DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 261' DV Tool Used?

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion. Other completion. NGPA filing

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Michael D. Weillert, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 21 day of March, 19 84.

(NOTARY PUBLIC)

MY COMMISSION EXPIRES:

\*\* The person who can be reached by phone regarding any questions concerning this information.

Side TWO  
OPERATOR

Weilert Oil Company

LEASE NAME Prewo

SEC 6 TWP 14 RGE 17 (W)

WELL NO 1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
Check if no Drill Stem Tests Run. <input checked="" type="checkbox"/> Check if samples sent Geological Survey.				
Sand & Shale	0	40		
Sand & Shale	40	276		
Sand & Shale	276	707		
Sand & Shale	707	1342		
Shale	1342	1595		
Shale	1595	1898		
Shale	1898	2033		
Shale	2033	2186		
Shale	2186	2303		
Shale & Lime	2303	2413		
Lime & Shale	2413	2550		
Lime & Shale	2550	2655		
Lime & Shale	2655	2743		
Lime & Shale	2743	2883		
Lime & Shale	2883	2960		
Lime & Shale	2960	3043		
Lime & Shale	3043	3109		
Lime & Shale	3109	3167		
Lime & Shale	3167	3247		
Lime	3247	3330		
Lime	3330	3345		
Lime	3345	3355		
Lime	3355	3400		
Lime	3400	3467		
Lime	3467	3541		
Lime	3541	3593		
T.D.	3593			
D&A				

If additional space is needed use Page 2

Report of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		261'	Common	140	3% Cal cl 2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (Flowing, pumping, gas lift, etc.)	Gravity
Estimated Production (bbl./day)	Oil	Gas
	Water	Gas-oil ratio
Disposition of gas (vented, used on lease or sold)		C/P/S

Perforations

Corrected copy 15-051-23804-00-00

SIDE TWO (Page Two)

ACO-1 WELL HISTORY

OPERATOR Weilert Oil Co, Inc LEASE NAME Prewo # 1 SEC. 6 TWP. 14 RGE. 17W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<b>DRILL STEM TESTS</b>				
D.S.T. #1-----Lansing-K.C.-----	3302'	3351'	Topeka	2985
RECOVERY: 90 feet of mud, with a few oil specks			Heebner	3248
			Toronto	3266
			Lansing-K.C.	3293
			K.C. Base	3521
Tool Open: 90 minutes I.F.P.-----	71-81	P.S.I.	Pennsylvania	
Tool Closed: 30 minutes F.F.P.-----	81-91	P.S.I.	Conglomerate	3529
Second Open & Close				
Tool Open: 15 minutes				
Tool Closed: 15 minutes				
D.S.T. #2-----Lansing-K.C.-----	3349'	3406'		
RECOVERY: 120 feet of watery mud with a show of gas				
Tool Open: 120 minutes I.F.P.-----	61'91'	P.S.I.		
Tool Closed: 30 minutes F.F.P.-----	91'-102'	P.S.I.		
Second Open & Close				
Tool Open: 60 minutes				
Tool Closed: 30 minutes				

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1984

CONSERVATION DIVISION  
Wichita, Kansas

15-051-23804-00-00

Office: (913) 625-2888  
Mobile: (913) 625-7806  
Residence: (913) 625-6327



2604-E General Hays Rd.  
Hays, Kansas 67601

# WEILERT OIL COMPANY, INC.

May 15, 1984

Kansas Corporation Commission  
200 Colorado Derby Building  
Wichita, KS 67202

Dear Sirs:

On March 21, 1984, we filed the affidavit of completion form for the Prewo lease. The information on Page 2 (Side 1) is incorrect. This information was unintentionally taken from another lease which was used as a reference guide in filling out the form. Enclosed is the original form filed and the corrected copy. Please correct your files. Thank you.

Sincerely yours,

Michael D. Weilert  
Weilert Oil Company, Inc.

bh

Enclosures

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 17 1984

CONSERVATION DIVISION  
Wichita, Kansas