

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Dreiling Ltd. of Colorado
 ADDRESS 410 - 17th St., Suite 1140
Denver, Colorado 80202

API NO. 15-051-22,617-60-00
 COUNTY Ellis
 FIELD WYOUNGER SW
 PROD. FORMATION Arbuckle

**CONTACT PERSON Floyd H. Hoffman
 PHONE (302) 623-6144

LEASE B; Younger
 WELLS NO. 1


PURCHASER Clear Creek
 ADDRESS P.O. Box 1045
McPherson, Kansas 67460

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 14 1981
 12-14-81
 CONSERVATION DIVISION
 WICHITA, KANSAS

WELL LOCATION SE NE NE
 Ft. from _____ Line and
 Ft. from _____ Line of
 the SEC. 7 TWP. 14S. RGE. 17W

DRILLING CONTRACTOR C and R Drilling Co.
 ADDRESS 410 - 17th St., Suite 1140
Denver, Colorado 80202

PLUGGING CONTRACTOR Halliburton
 ADDRESS Hays, Kansas



WELL PLAT
 KCC
 KGS
 MISC
 (Office Use)

TOTAL DEPTH 3600 PBTD _____
 SPUD DATE 10-17-81 DATE COMPLETED 12-6-81
 ELEV: GR 1994 DF _____ KB 1999

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.
CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	206'	Reg. Portland	125	2% Gel & 3% C1
Production	7-7/8"	4-1/2"	9 1/2#	3600'	Reg. Portland	125	Salt gran. blended Cal Seal blended
1240'-Surf. (FO Tool)- cemented from Anhydrite to surface						300	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	43"	3538'-3550'

TUBING RECORD


Size	Setting depth	Packer set at
2-3/8"	3565'	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/4000 Gal. 20% MOD-202	3538'-3550'

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
December 6, 1981	Pumping	
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas
	10 bbls.	Trace
Disposition of gas (vented, used on lease or sold)	Water	Gas-ill ratio
Vented	75 %	30 bbls.
	MCF	
	Perforations	
	3538'-3550'	

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.



Name of lowest fresh water producing stratum _____ Depth 48'

Estimated height of cement behind Surface Pipe Circ. to Surf.

DV USED? FO Tool used

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
ANHYDRITE	1202'	1243'	ANHYDRITE	1202
TOPEKA- Shale and limestone	2980'	3251'	TOEPAK	2980
HEEBNER- Shale and limestone	3251'	3268'	HEEBNER	3250
TORONTO- Shale and limestone	3268'	3295'	TORONTO	3268
LANSING- Limestone and shale	3295'	3509'	LANSING	3295
BASE L-KC- Shale and limestone and sandstone	3509'	3531'	BASE L-KC	3509
ARBUCKLE- Dolomite	3531'	3600'	ARBUCKLE	3531
DST 3525'-3540' 15-30-30-30 Rec. 7' MCO FP 8-24#, 18-31# SIP 817-641#				
DST 3534'-3546' 15-30-30-60 Rec. 31' MCO FP 15-25#, 29-35# SIP 1085-1092, 1060-1065#				

AFFIDAVIT

STATE OF COLORADO, COUNTY OF DENVER SS,

Floyd H. Hoffman OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Exploration Manager (FOR)(OF) Dreiling Ltd. of Colorado

OPERATOR OF THE B. Younger LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 6th DAY OF December, 1981, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(s) Floyd H. Hoffman

SUBSCRIBED AND SWORN BEFORE ME THIS 11th DAY OF December, 1981

Lorraine C. Murphy
NOTARY PUBLIC

MY COMMISSION EXPIRES: Sept. 2, 1983

