

15-051-20382-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED  
JAN 10 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
01-10-69

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Three G Oil, Inc.

Complete Address: 1101 Wichita Plaza Wichita, Kansas

Lease Name Schulte Well No. 1

Location NW SW NE Sec. 1 Twp. 14 Rge. 16 (E) (W) XX

County Ellis Total Depth 3420

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Dunne - Gardner

Address: Wichita, Kansas License No. 526

Operation Completed: Hour 7P Day 5 Month 1 Year 1968

The Above well was plugged as follows:

RTD 3420' 8 5/8 csg set at 240' cwc 275 sk. Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 450' and displaced 50 sk cmt.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cement to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Morsey  
Well Plugging Supervisor

INVOICED

DATE 1/10/69  
INV. NO. 9172-W