

15-051-30259-00-61

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aspen Enterprises, Inc.
Complete Address P.O. Box 516 Great Bend, Kansas 67530
Lease Name Younger Well No. 1
Location SE SW NE Sec. 6 Twp. 14 Rge. (E) (W) 17
County Ellis Total Depth 3622
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Forbes Casing Pulling
Address Box 221 Great Bend, Kansas License No. 637
Operation Completed: Hour Day 3 Month 5 Year 1970

The above well was plugged as follows:

Total Depth 3622' 8 5/8 csg set at 218' cwc 155 sk.

5 1/2 csg set at 3621' cw 75 sk cmt.

5 1/2 csg top perf. (3562)

Filled 5 1/2 csg W/sd (3550-3622) Dumped 5 sk cmt W/dump bailer. (3510-3550)

Shutoff and recovered 2214' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 130 sk

50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. D. Massey
Well Plugging Supervisor

DATE 5/4/70

INV. NO. 1830-W