

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 15LOCATION NE NE SESEC. 6 TWP. 17S RGE. 17WDry Hole Portary Abandoned Oil Well - Abandoned Gas Well -

I have today completed supervision of plugging of:

Well No. 1 Lease YoungerOperator Deland Oil & Gas Co. Address 308 North B. Tulsa Okla.Field - County EllisTotal Depth 3574 Feet.

(Describe briefly the manner in which the well was plugged)

The hole was filled with heavy mud
3574 ft to bridge at 3294 ft cement 3294 ft to
3260 ft 5 ray heavy mud 3260 to bridge at 750 ft
cement 750 ft to 720 ft 10 ray mud 720 ft to
252 ft cement 250 to 220 ft 10 ray mud 220 ft to
10 ft cement to base of cellar, 1300 ft 8% cement
left in hole

A. W. Kern
District Conservation Agent

Date Oct 17-75

11-02-45

6 14 17W
28 19