

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 051- 22,693-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Dreiling LTD. of Colorado

Complete Address 410 17th St., Suite #1140, Denver, Colorado 80202

Lease Name Wasinger Well No. #1

Location NW-SE-NW Sec. 7 Twp. 14 Rge. 17 (East) (West)

County Ellis Total Depth 3618'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor C & R Drilling Company

Address 410 17th Street, Suite #1140, Denver, Colorado 80202 License No. _____

Operation Completed: Hour: 2:00PM Day: 3rd Month: Dec. Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-206' s.p. cuc. w/130 sacks common-2% Gel.-3% Cal. Cl.

Ordered 135 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole and 5 sacks in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION

DEC - 7 1981
12-07-81

CONSERVATION DIVISION

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 1-19-82

8921-W