

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JAN 17 1977
01-17-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-051-21,252-00-00 (of this well)

Operator's Full Name A. Scott Ritchie

Complete Address 125 N. Market, Suite 950, Wichita, Kansas

Lease Name Younger Well No. 1

Location NW NE NE Sec. 7 Twp. 14 Rge. (E) (W) 17

County Ellis Total Depth 3584'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 5:15 P Day 14 Month 1 Year 1977

The above well was plugged as follows:

RTD 3584' 8 5/8 csg set 211' cwc 150 sx. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Les Massey
Well Plugging Supervisor

DATE 1-17-77

INV. NO. 4490-W