

15-051-00128-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 47-5

LOCATION NE NE NE

SEC. 7 TWP. 14 RGE. 17

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Younger 709 Union Natl Bldg. Bldg.

Operator Anschutz DrgbCo Address Wichita, Kans

Field _____ County Ellis

Total Depth 3606 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 147' circulated with cement - 5 1/2" at 3526'

with 75 sax cement behind - Rock to 3520', set 5 sax cement

with dump bailer, pulled 2620' 5 1/2", Pumped in 25 sax

Halcogel filling hole with mud, pumped in 50 sax cement

filling hole with cement 150' to 0', pump pressure 300#,

Mudding and cementing by Halliburton Co.

PLUGGING
FILE SEC 2 T 14 R 11
BOOK PAGE 47 LINE 5

RECEIVED
STATE CORPORATION COMMISSION
OCT - 1 1952
10-01-52
CONSERVATION DIVISION
Wichita, Kansas

Ed. J. [Signature]
District Conservation Agent
Date 9-27-52