

15-051-20917-60-00

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Imperial Oil Company

Complete Address: 780 4th National Bldg., Wichita, Kansas

Lease Name Younger "B" Well No. 1

Location C W/2 SW NE Sec. 7 Twp. 14 Rge. (E) (W) 17

County Ellis Total Depth 3605'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 12:30P Day 25 Month 10 Year 1969

The Above well was plugged as follows:

RTD 3605' 8 5/8 csg set at 209' cwc 175 sk Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 450' and displaced 50 sk cmt
thru drill pipe. Heavy mud to 200' set cementing plug and displaced 25 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/27/69
INV. NO. 727-4

Signed: Leo F. Messer
Well Plugging Supervisor