

15-091-00344-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1960
08-30-60
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: SW NW NE Sec. 7 Twp. 14 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3565

I have this date completed supervision of plugging of:

Lease Name: Younger Well No. 1

Operator's Full Name: Davis Bros

Complete Address: 14 E 3rd Tulsa, Okla

Plugging Contractor: Barnes & Sons & Halliburton Co

Address: Russell, Kans License No. 9

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes No

If yes how long? _____ Reason: _____

Operation Completed: Hour 1PM Day 22 Month 8 Year 60

The above well was plugged as follows:

8 5/8" 165' circulated with cement - 4 1/2" 3553' with 150 sax cement.

Set 4 sax cement on bottom with dump bailer, pulled 2940' 4 1/2"

Pumped hole full heavy mud (40 sax Gel), pumped cementing plug to 475'

followed by 150 sax cement - cement 475' to 0'.

Mudding and cementing by Halliburton Co - 500# to 300# pump pressure.

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 8/31/60
INV. NO. 1863-W