

15-167-00070-00-00

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 6-14

LOCATION SW-SW-SW

SEC. 14 TWP. 14 RGE. 13W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Jones "C"

Operator Duke & Wood Drly Co. Address Box 123 Mt. Bend Kans.

Field _____ County Russell

Total Depth 2380 Feet.

Plugging Contractor Alc Pipe Pulling Co.

Plugging Contractor's License No. 2

Address Great Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" @ 246' c.w.c. Oil string 5 1/2" @
2379' w/ 75 sx cem. P.B. w/ cem to 2359' Top Ref.
2340' Filled back with sand to 2330' and
dumped 5 sx cem. with dump bailer. Shot off and
pulled approx 1700' of 5 1/2" casing. Filled hole with
mud to 240' set rock bridge and run 20 sx cem.
mud to 35' rock bridge and 10 sx mixed cem
to base of collar.

PLUGGING
FILE SEC 14 T 14 R 13W
BOOK PAGE 6 LINE 14

RECEIVED
CONSERVATION COMMISSION
JAN 23 1954
01-28-54
CONSERVATION DIVISION
Wichita, Kansas

Warren G. Horner
District Conservation Agent

Date 1-26-54