

15-167-00177-00-01

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 20-25LOCATION SW-NW-SWSEC. 10 TWP. 14 RGE. 13WDry Hole ☒ Abandoned Oil Well ☐ Abandoned Gas Well ☐

I have this date completed supervision of plugging of:

Well No. 1 Lease BollerOperator Gen Addis Address 120 maple st
Russell KansField County RussellTotal Depth 2387 Feet.Plugging Contractor Jayhawk Casing Pulling Co.Plugging Contractor's License No. 19Address Russell Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" @ 208' C.W.C. Oil string 5 1/2"
@ 2386 set w/125 sx Cem. Top perf in Casing
at 2350. Filled back with sand to 2340'
and dumped 5 sx Cem. shot off and pulled
5 1/2" casing. Mud to 200' rock bridge and
20 sx of Cem with dump hauler. mud to 35'
s. bridge and 10 sx mixed Cem. to surface.

RECEIVED

STATE CORPORATION COMMISSION

MAR 25 1954

CONSERVATION DIVISION

Wichita, Kansas

Warren H. Horner
District Conservation Agent

Date Mar 22, 1954

PLUGGING

FILE SEC 10 T 14 R 13W
BOOK PAGE 20 LINE 25