

15-167-00044-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-SW-SW

SEC. 7 TWP. 14 RGE. 13W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Crowe A

Operator H.B. Shumaker Address Russell Kans

Field _____ County Russell

Total Depth 2443 Feet.

Plugging Contractor Jayhawk Casing Pulling Co.

Plugging Contractor's License No. 19

Address Russell Kans

(Describe briefly the manner in which the well was plugged)

Surface pipe left in hole. None. 7" OD Oil string set 2443 w/ 75 sq ccm. Ccm drilled out to 2383'. Top perf. 2370' filled back with sand to 2360' and dump 5 sq ccm. Shot off and started pipe. pumped in 15 sq of fresh gell mud pulled casing to 200' and pumped in 40 sq of ccm. mud to 30' rock bridge and 10 sq of ccm to base of cellar. Ccm mixed by Halliburton

Warren D. Harner
District Conservation Agent

Date Feb 26, 1954

FEB 1 - 1954
02-01-54
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 7 T 14 R 13W
BOOK PAGE 15 LINE 7