

OCT - 1 1981

CONSERVATION DIVISION
FORM CP-2
Wichita, Kansas

State of Kansas



15-167-21780-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSONGovernor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Leonard Williamson of Duke Drilling Co., Inc. has this
date requested permission to plug the following described well:

Operator's Full Name: Orville KaufmanComplete Address: RFD#1, Great Bend, Kansas 67530Lease Name: Lester Well No. #1Location: SE/NE/NE SEQUOIA AUBRE Sec. 30 Twp. 14 Rge. 11 (E) (W)County: Russell Total Depth: 3207'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A xxOther well as hereafter indicated: Mr. Leonard Williamson was instructed to plug the well as follows:

8 5/8"-250' sp. cuc. w/165 sacks common-50/50 posmix-2% Gel.-3% Cal. Cl.
Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug. Spotted
with drill stem with heavy med between all plugs.

1st plug @ 720' w/70 sacks cement2nd plug @ 240' w/40 sacks cement3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement5 sacks of cement in rat hole.

Very truly yours,

Conservation Division Agent