



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 12 1972  
06-12-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Damme of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Kenneth Rupp guarantees payment of the plugging fee.

Operator's full Name: Kenneth Rupp

Complete Address: 420 Union Center, Wichita, Kansas 67202

Lease Name: Bunker Well No. # 1

Location: NW SE <sup>NE</sup> SE Sec. 28 Twp. 14 Rge. 11 (E)(W) W

County: Russell Total Depth 3200 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Fred Damme was instructed to plug the well as follows:

8 5/8" csg. 208' Cwc.

Circulated hole with heavy mud to 400' & displaced 40 sax cement thru drill pipe. Mud to 200' & displaced 25 sax cement thru drill pipe.

Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with

Allied Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don. L. ...  
Conservation Division Agent